



ALL C PURLINS IN THE OFFICE ROOF BETWEEN GRIDS G & H ARE TO BE ERECTED ON THE HIGH SIDE OF THE CLEAT WITH THE TOES FACING NORTH

THE C PURLINS BETWEEN GRIDS F & G & 1 & 4 ARE TO BE ERECTED ON THE HIGH SIDE OF THE CLEAT WITH THE TOES FACING TOWARDS THE APEX

**ERECTION NOTES**

1. ERECT HORIZ. & DIAG. MEMBERS WITH THEIR ASSEMBLY MARK ON TOP FACE & ON THE SAME END AS SHOWN ON THIS PLAN.
2. FIN PLATES FOR CHANNELS ARE ON HEEL UNLESS SHOWN OTHERWISE.
3. FIN PLATES FOR BEAMS WILL BE ON NORTH OR WEST SIDE OF BEAM WEB, UNLESS SHOWN OTHERWISE, i.e. ERECT BEAMS TO SOUTH OR EAST SIDE OF CLEAT.

**G & R SHOP DETAILING**  
 11 The Boulevard Ph. 07 34082944  
 Bribie Island. Fx. 07 34080151  
 Qld. 4507. graeme@grshopdetailing.com.au

**TEKLA Structures®**

PROJECT		LOT 2 PROSPECT PLACE BERRINBA	
CLIENT		B & L STEEL P/L	
DRAWN	GP	SCALE	1:80
CHECKED		DATE	16.05.2008
DRAWING No.			227 - MP4
REV			B

**PURLIN MARKING PLAN**

B	ISSUED FOR FABRICATION	05-06-08
A	ISSUED FOR APPROVAL	15-05-08
REV	REVISION DESCRIPTION	REV. DATE